

ISOMETRIC VIEW


NOTES: UNLESS OTHERWISE SPECIFIED.


- 1. ALL DIMENSIONS ARE IN DECIMAL INCHES.
- 2. PRE-CAST CONCRETE MATERIALS AND MANUFACTURING METHODS SHALL CONFORM TO ASTM C-478.
- 3. CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH F C= 4000 PSI AT 28 DAYS.
- THE PORTLAND CEMENT USED IN THE PRE-CAST SECTIONS SHALL MEET THE REQUIREMENTS OF TYPE V HIGH SULFATE RESISTANT CEMENT IN ACCORDANCE WITH ASTM C-150.
- 5. PRE-CAST JOINTS SHALL BE SEALED USING MASTIC. NOTE: RUBBER GASKET AVAILABLE ON 84.00 AND LARGER MANHOLES.
- 6. OPTIONAL: PIPE TO MANHOLE CONNECTIONS SHALL BE MADE USING X-CEL, A-LOK OR Z-LOK FLEXIBLE CONNECTORS BY A-LOK PRODUCTS. CONNECTORS SHALL MEET THE REQUIREMENTS OF ASTM C-923.
- CONTRACTOR SHALL SEAL ALL PENETRATIONS MADE AT JOB SITE AND OR NOT SHOWN ON PLANS.
- 8. ACCESS COVER PER SEPARATE SUBMITTAL.
- 9. FILLET IS CONSTRUCTED AS A SECONDARY POUR.
- 10. PUMPS, PIPING AND HARDWARE BY OTHERS.

Phone (805) 527-0841 Fax (805) 584-0769 PUMP STATION, 72.00 DIA-W/VAULT


> MODEL NO. SH 1 OF 5 12/14/2005

> > H:\MH\PS Std-Catalog\PS72V-STD Vault.idv





PUMP STATION PLAN SECTION VIEW







TITLE

PUMP STATION, 72.00 DIA-W/VAULT

 APPROVED BY
 DATE
 APPROVED BY
 DATE
 DRAWN BY
 DATE
 MODEL NO.

 F. ANSALDI
 12/14/2005
 PS72V-STD
 SH 3 OF 5

