



NOTES: UNLESS OTHERWISE SPECIFIED.

- MANUFACTURING METHODS AND MATERIALS FOR PRECAST UNITS SHALL CONFIRM WITH ASTM C-478 AND LA CITY STANDARD S-140-AND S-142.
- 2. PRECAST MATERIALS AND MANUFACTURING METHODS SHALL CONFORM TO ASTM C-478.
- 3. CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH F C= 4000 PSI AT 28 DAYS, MIX DESIGN # 1419017, MIX DESCRIPTION 660-CW-4000P PRE-CON MIX.
- 4. THE PORTLAND CEMENT USED IN THE PRECAST SECTIONS SHALL MEET THE REQUIREMENTS OF TYPE II/V HIGH SULFATE RESISTANT CEMENT IN ACCORDANCE WITH ASTM C-150.
- 5. TYPE 1 LINING SHALL BE INSTALLED BY CERTIFIED INSTALLERS.
- 6. LANE EZ LIFT PINS AND CONAC A-ANCHORS ARE USED FOR LIFTING. GROUT OVER HOLES AFTER INSTALLATION OF MAINTENANCE HOLES.
- 7. REINFORCING HOOPS AREA .25 GRADE 60 INSTALLED EVERY 12" PER ASTM C 478 AND ASTM A 615.
- 8. MAXIMUM HEIGHT 35 FEET, SEE PROJECT PLANS IF THE HEIGHT EXCEEDS 35 FEET.
- 9. ALL JOINTS TO BE SEALED USING CLASS "C" MORTAR OR APPROVED PREFORMED FLEXIBLE JOINT SEALANT. SEALANT SHALL MEET OR EXCEED ASTM C 990.

DATE

- 10. RING AND COVER SHALL BE GREY CAST IRON A-1496 MARKED "S".
- 11. MANHOLE COMPLIES WITH HS20 TRAFFIC LOADING.

APPROVED BY

- 12. THE STRUCTURE WAS NOT DESIGNED TO RECEIVE SURCHARGE LOADS FROM ADJACENT STRUCTURES OR RAILROAD LOADS.
- 13. CONTACT BUREAU OF CONTRACT ADMINISTRATION MATERIAL CONTROL SECTION AT (213) 847-2442 FOR FABRICATION INSPECTION.

14. A COPY OF PRODUCTION APPROVAL TO BE AVAILABLE AT PRECON PRODUCTS MANUFACTURING PLANT AND JOB SITE AT ALL TIMES.

15. SEE CITY OF LOS ANGELES APPROVED PRODUCTS LIS FOR APPROVED TYPE 1 LINING AND APPROVED PREFORMED FLEXIBLE JOINT SEALANT.

APPROVED BY



KSTRADER 6/2/2021